

जीवाजी विश्वविद्यालय, ग्वालियर

कोटेशन आमंत्रण पत्र

क्रमांक/एफ.जे.यू./यंत्रि/2022/09

दिनांक: - 13/01/2022

प्रति,

विषय :- जीवाजी विश्वविद्यालय के आवास क्रमांक एल-05 चैनलिंग फैसिंग का कार्य कराये जाने
बावत्

महोदय,


जीवाजी विश्वविद्यालय के आवास क्रमांक एल-05 चैनलिंग फैसिंग का कार्य कराये जाने हेतु दरें आमंत्रित की जाती हैं। कृपया आप अपनी दरें दिनांक 28-01-2022 सायं 5:00 बजे तक सील बंद लिफाफे में सीधे ही/स्पीडपोस्ट/पंजीकृत डाक के माध्यम से कुलसचिव जीवाजी विश्वविद्यालय ग्वालियर के पते पर भेजे। लिफाफे पर कोटेशन, कार्य का नाम तथा अंतिम तिथि आवश्यक रूप से अंकित करें,

| सं. क्र. | एस.ओ. आर. क्रमांक | विवरण | मात्रा | दर |
|----------|-------------------|--|---------------|----|
| 01 | 2.6 | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30cm in depth, 1.5m in width as well as 10 sqm on plan) including dressing of sides and ramming of bottom disposal of excavated earth, lead up to 50m and lift up to 1.5m, disposed earth to be levelled and neatly dressed. (No extra lift is payable if work is done by mechanical means) All kinds of soil . | 1.22 cum | |
| 02 | 4.1.1.3 | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work upto plinth level : | 1.22 cum | |
| 03. | 10.29.2 | Supplying at site: Angle iron post and strut of required size including bottom to be split and bent at right angle in opposite direction for 10 cm length and drilling holes upto 10 mm dia. etc. complete. (cost of earth work in excavation and concrete work in foundation to be paid separately) | 594.24 Kg. | |
| 04. | 10.34.1 | Providing and fixing G.I. coated G.I.wire chain link fabric fencing of required width and mesh size including strengthening with 2mm dia wire or nuts, bolts and washers as required complete with posts of specified material and of standard design placed and embedded in cement concrete blocks 45x45x60cm of mix 1:5:10 (Cement :5 sand :10 graded stone aggregate 40mm nominal size) every 15th post, last but one end post and corner post shall be strutted on both sides and end post on one side only and struts embedded in cement concrete | 180.18 Kg. | |

| | | | | |
|-----|-------|---|--------|-----|
| | | blocks 70x45x50cm of the same mix, as per the direction of Engineer- in-charge. (Cost of post, painting earthwork & c.c. to be paid separately) Made of G.I. wire. | | |
| 05. | 13.64 | Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work. . | 116.25 | sqm |


शर्तें :-

1. सामाग्री की मात्रा आवश्यकतानुसार घटाई व बढ़ाई जा सकती है।
2. फर्म के नाम पैन नम्बर/टिन नम्बर/जी.एस.टी.नम्बर होना आवश्यक है।
3. कुटेशन स्वीकृत/अस्वीकृत करने का अधिकार कुलसचिव विश्वविद्यालय के पास सुरक्षित रहेगा।
4. कुटेशन अंतिम तिथि तक वि.वि. में रजिस्टर्ड डाक से प्राप्त हो जाने चाहिये।


कुलसचिव

प्रतिलिपि :-

1. श्रीमान संजय बरथरिया की ओर वेबसाइट पर अपलोड करने हेतु प्रस्तुत है।


वि.वि.यंत्री