

CENTRAL LIBRARY
Jiwaji University Gwalior-474011

Ref No. LB/2394/18

Date 28/9/18

QUOTATION CALL LETTER

To,

.....
.....
.....
.....

To carry out UTP Cabling work in computer Lab situated in central library following items with given specifications and quantity are to be purchased and installed.

Kindly submit the quotation indicating the reasonable rate with the discount to an educational institution if any.

The quotation must reach the Registrar Jiwaji University Gwalior by October 6, 2018 by speed post during office hours.

A. Supply Item Detail

Sr.No.	Description	Qty
1	12 Port LIU with LC type SM Coupler	02 Unit
2	SFP optical module transceivers Dual data rate 1.25Gbps, 1550nm transmission upto 120km, 3.3v single power supply compatible with sonnet, ROHS	02 Unit
3	Optical Fiber Cable 6 Core Armored 9/125um double sheath, csta, unitube outdoor cable	80 Mtr
4	Optical Fiber Connector LC Type	12 Unit
5	Optical Fiber Pigtail single mode 1m LC Type	12 Unit
6	Optical Fiber Patch Cord 3m LC Type 9/125 um	02 Unit
7	22U Floor Standing Rack Overall height 1160 Overall width-600 Static Load 150kg 977.9mm, cooling fan, 6 socket power distribution unit	01 Unit
8	information Outlet with keystone, faceplate RJ-45 -50u compliant with ANSI/TIA 568-C.2 Suitable 22-26 AWG Wire	105 Unit
9	24 Port Jack Panel category 6 Supported 1U Panel, PC+ Glass fiber UL 94V	05 Unit
10	Cable manager standard size 1U with 4 cable Griper	05 Unit
11	24 Port Gigabit Manageable switch with 2 SFP Port Switching Capacity in Gbps 56.0, Dual IPv6/IPv4 stack ACLs- 512 rules, Support for CIDR	05 Unit
12	UTP Cable Roll with 305m length Supports Gigabit Ethernet 1000 base T performance 600 Mhz, operating voltage 72V, thickness 0.2mm	12 Box
13	UTP Patch Cord 2m	105 Nos.
14	UTP Patch cord 1m for Jack Panel	105 Nos.
15	HDPE Pipe 25 MM	80 Mtr.

28/9/18
Registrar

[Signature]
28.9.18


B. Installation Detail


Sr.No.	Description	Qty
1	Installation & termination I/O	105 Unit
2	Installation & termination UTP Cable on jack Panel	105 Unit
3	Fixing of 22U Rack On Floor	01 Unit
4	Splicing of fiber cable	12 Core
5	Laying Of UTP/OFC cable with conduit pipe	3660 Mtr
6	Heinshn Digging and Tilling (HDT Shots) if required	20 mtr
7	Labor (Trenching) 2.5 Feet depth	60 Mtr

General terms and conditions applicable for all items:

1. Rates quoted should be inclusive of all taxes and other charges for delivery , installation and **F.O.R. Jiwaji University, Gwalior.**
2. Vendors are advised to read specifications carefully and submit quotations as per the specifications given only.
3. Quotation received after due date will not be considered
4. The complete detailed specifications along with accessories, if any, be clearly mentioned in the quotation giving the guarantee/ warranty period. Facilities for service should also be indicated. Detailed technical information, Brochures, leaflets, and drawings whichever is applicable must be furnished along with quotation.
5. All network point installed will have be maintained for Two Year by the venders .

IT cell please upload on University website.


28.9.18.




Registrar